## KEY

ZONE 0
ZONE 20
ZONE 1
ZONE 21
ZONE 2
ZONE 22

## NOTES

1. MINIMUM EQUIPMENT STANDARD FOR DUST HAZARDS TO MEET INGRESS PROTECTION (IP) RATING OF 5X (ZONE 22) AND 6X (ZONE 21) AND A MAXIMUM SURFACE TEMPERATURE OF 205°C BASED ON 280°C (LIT) - 75°C = 205°C.

2. A ZONE 21 WITHIN THE BUCKET ELEVATOR. REFER [1] TABLE 2.

3. A ZONE 22 OF A 1m RADIUS DOWN TO GROUND FROM HOUSEKEEPING / INSPECTION HATCHES. REFER [1] TABLE 2.

## REFERENCES

- [1] 7619_REP01 ROYAL SEAFORTH GRAIN TERMINAL DSEAR HAZARDOUS AREA CLASSIFICATION REPORT.

| | |
|---|---|
| REVISION | A |
| DATE | 15/06/20 |
| DESCRIPTION | AS BUILT |
| AUTHOR | HR |
| CHECKED | SDO |
| APPROVED | AW |

INGLEWOOD ENGINEERING CONSULTANCY LTD
SYCAMORE HOUSE,
SPRINGWOOD WAY,
TYTHERINGTON BUSINESS PARK,
MACCLESFIELD, CHESHIRE,
SK10 2ND, 01625 410100
INFO@INGLEWOODENGINEERING.COM

PROJECT
DSEAR AREA CLASSIFICATION
IEC PROJECT No. 7840
IEC DRAWING No. 7840-73-00025

| SCALE | | | |
|---|---|---|---|
| NTS @ A3 | DRAWN | H. RAZA | DATE 15/06/20 |
| | CHECKED | S. OWEN | DATE 29/06/20 |
| | APPROVED | A. WOOD | DATE 09/07/20 |

TITLE
ROYAL SEAFORTH GRAIN TERMINAL
GENERIC INSPECTION HATCH
AREA CLASSIFICATION DRAWING

DRAWING No. 7840-73-00025 SHT No.

REV. A